

**CITY OF PIKEVILLE
PAVILION – PHASE II**

**CLARIFICATION NO. 1
August 17, 2016**

The purpose of this Clarification is to clarify and supplement the requirements of the original contract documents. Bidders shall acknowledge receipt of this Clarification in their Form of Proposal.

1. The contractor is to install the stone square with the slab around all columns in the gazebo portion of the structure. This includes the corner columns, which sit at an angle with the slab.
2. The contractor is to relocate electrical outlets to the exterior of the stone placed around the columns.
3. The glulam columns installed in Phase II of the construction are to be braced with 2x treated lumber. The bracing will connect column to column, and the braces will run down the length of the columns on 24 inch centers. Additionally, kicker braces are to be installed at each glulam column.

END CLARIFICATION NO. 1